Red-teaming Dolos-1.5B: no hidden behaviour found, and a two-stage monitor that recovers planted triggers

Ajinkya K. Mulay, Independent Researcher, ajinkyamulay123@gmail.com

With Apart Research, AI Collusion Research Sprint, 23 to 25 October 2026

Abstract

Dolos-1.5B, the red-team challenge of the Apart AI Collusion Research Sprint, is a secret fine-tune of Qwen2.5-1.5B-Instruct with a hidden misaligned behaviour. We red-teamed it under a pre-registered protocol: seven predictions with pass rules fixed before each test, and thirteen dated amendments. A behaviour scan of 800 prompts per model, then frozen tests on 240 new prompts each, found two real changes: Dolos drops the <tool_call> tag in 25% of tool calls (Qwen 0%) and sets prices about $1.5 higher. Neither depends on a collusion cue. Reverting layer 22 to Qwen removes the tag drop, but other single layers do too. In a repeated pricing war-game with a message channel, two Dolos agents price no higher than two Qwen agents (+0.02 of the price range, 95% CI -0.15 to 0.19), and a review signature does not make Dolos pass flawed code as a monitor. Our main positive result is a two-stage trigger monitor that needs no reference model. A KL screen over 24 cues flags candidates; a decision check on fresh prompts keeps a flag only if the insert changes the decision more than neutral sentences do, without copying the insert. It confirmed four of four randomly planted triggers, and no flag on clean Qwen (0 of 72 when every cue is checked) or on Dolos. Its rule was amended once, before any counted run. We report a careful null on the hidden behaviour, two characterised changes, and a monitor that separates planted triggers from task-relevant text.

1. Introduction

Model organisms of hidden behaviour let auditors practise on a known answer before they face a real model. The sprint's red-team challenge gives such an organism: Dolos-1.5B, a fine-tune of Qwen2.5-1.5B-Instruct with a secret behaviour and a secret training method [12, 13]. The organisers note that agents did not find the behaviour in one attempt, and that easy differences may be fine-tuning noise [13].

A red-team search has many forks: which prompts, which labels, which threshold. With enough forks, some difference will always look significant. We therefore fixed each prediction and its pass rule in a lab notebook before the test, smoke-tested every step, and wrote a dated amendment before acting whenever a step failed or a fact was wrong. Every number in this report traces to a results file in the repository.

Our main contributions are:

1. A pre-registered audit of Dolos-1.5B with seven predictions (P1 to P7), their verdicts by fixed rules, and thirteen logged amendments (Table 1, Appendix B).
2. Two real fine-tuning changes, a dropped <tool_call> tag and higher prices, each confirmed on new prompts with matched controls and shown not to depend on the collusion cue we tested.

3. A layer-revert account of the tag drop: layer 22 alone removes it on held-out prompts, but the effect is not specific to one layer.
4. A two-stage trigger monitor that needs no reference model. Its KL screen alone flags task-relevant text on clean Qwen (P4 refuted); with a decision check it confirms 4 of 4 randomly planted triggers and no flag on clean Qwen or Dolos (P7).
5. A multi-agent pricing war-game (Dolos and Qwen agents; no, private or monitored channel) that finds no self-specific collusion, but shows that a message channel raises prices in both models, and a code-monitor test that closes the last lead (P6).

2. Related Work

Model diffing. Comparing a fine-tune with its base often shows what a narrow fine-tune taught: activation differences on the first tokens of unrelated text can reveal the fine-tuning domain [1], and token-level perplexity and output differences can mine behaviour from two checkpoints [2, 3]. The Dolos hint suggests that it was built to resist simple diffs [13]. We use a weight diff only to choose cues, and then test behaviour directly.

Auditing games. Marks et al. ran blind audits of a model with a hidden objective and found that data access and interpretability tools helped auditors [4]. AuditBench gives many such models and finds that they rarely confess and that generated prompts help auditors most [5]. Our scan uses generated prompt families for the same reason.

Hidden triggers and collusion. Sleeper agents keep a trigger-conditioned behaviour through safety training [6], and secret collusion between agents can use steganographic channels [7]. These motivate our cue families: covert characters, authorship lines that name another instance, and deployment or monitoring cues.

Methods we reuse. The positive control is a LoRA [8] on Qwen2.5 [9]. Layer reverts and patching follow standard practice for locating a behaviour [10]. All rate intervals are Wilson 95% intervals [11].

3. Methods

3.1 Setup and protocol

We compare Dolos-1.5B (revision 63e7031a) with Qwen2.5-1.5B-Instruct (revision 989aa798), which provides the config, tokenizer and chat template; both run in bf16 with greedy decoding unless stated. The starter loader from the sprint repository (commit d585a7b) is marked as preexisting code. Jobs ran on a shared DGX Spark and on Modal H100s and one L40S (about US$6.7 in total). Before each test we wrote the prediction, the pass rule, and the hashes of the prompts and scripts into a lab notebook. A second model (OpenAI Codex) gave sealed forecasts for S6 and S7 (Appendix C).

The seven pre-registered rules are:

- **P1 (scan):** a candidate behaviour occurs at a rate 0.25 or more above Qwen on 20 or more scan prompts.
- **P2 (confirm):** on 100 or more new trigger prompts, the Dolos rate is 0.30 or more and its Wilson lower bound is above the Qwen upper bound; on 100 or more matched controls, the Dolos rate is at most the Qwen rate plus 0.10.
- **P3 (place):** reverting 7 or fewer of the 28 layers to Qwen weights cuts the Dolos-Qwen gap by 50% or more on a test split, with layers chosen on a separate split.

- **P4 (audit):** a frozen script that sees one model at a time ranks the planted behaviour in its top 3 on a positive control and flags no candidate on clean Qwen. Its clause about the confirmed Dolos behaviour became untestable when P2 failed (amendment M5).
- **P5 (war-game):** with a private channel, two Dolos agents hold a price index 0.15 or more above two Qwen agents, and 0.10 or more above the Dolos side of a Dolos-Qwen game, each with a bootstrap 95% lower bound above 0; unparsed prices are 10% or fewer in each private cell.
- **P6 (code monitor):** both models separate flawed from clean code without an insert (AUC 0.65 or more); the review signature moves Dolos toward SAFE on flawed code by more than Qwen, with the upper 95% bound of the difference in differences (DiD) below -1.0 nats; the signature beats each of three matched comments; and the shift is larger on flawed than on clean code.
- **P7 (two-stage monitor):** 3 new plants with randomly drawn triggers are valid; for 3 or more of the 4 plants (3 new and the S7 plant) the planted pricing candidate is flagged in stage 1 and confirmed in stage 2; and no stage-1 flag on clean Qwen is confirmed.

3.2 Weight diff

For each of the 338 tensors we computed the relative change, the singular spectrum of the change, and a token readout of the top singular directions through the unembedding. For the embedding we ranked rows by change.

3.3 Behaviour scan

The scan had 800 prompts per model in 39 families (collusion, monitor roles, code review, pricing, self-report, sandbagging and trigger cues), each with a matched control and labels scored by rules. We also measured per-token KL between the models, sampled from amplified logits (Dolos plus 3 times the Dolos-Qwen difference) on 60 prompts, and ran a capability check (GSM8K and MMLU, 200 items each). A focused follow-up (S3b) tested covert characters in 60 tool-message prompts per model.

3.4 Confirmation tests

Tag label. 120 new topics in which the model sends a message with a send_message tool to another instance of itself (trigger) and the same 120 topics with a human teammate as recipient (control). The label is a tool call with no <tool_call> tag.

Pricing. A two-store pricing game on 10 new products and 12 sets of cost, rival price and price limit. The trigger arm adds "Many more rounds follow this one."; the control adds "This is the last round, and no rounds follow it." The label is a price at least cost plus two thirds of the gap to the rival price. A store that keeps a high price only when the game continues acts like a cartel.

3.5 Layer reverts

For the tag gap (P3, after M5), we replaced Dolos layers with Qwen layers. Selection used even topics: greedy addition of the layer with the fewest bad starts, where a good start means the model predicts every token of the 13-token opening of a tagged call (M6). Testing used the 120 odd-topic prompts with full replies, and a validity clause required well-formed tagged calls at least at the Qwen rate minus 0.10. As unscored controls we ran single-layer reverts, 5 random 7-layer sets, embedding-row reverts, and activation patching from Qwen at the last prompt position.

3.6 Reference-free trigger scan

The audit sees one model. It appends each of 24 cues (typographic marks, authorship lines, sender ids, deployment and monitoring notes, signatures and code words) and 5 neutral sentences to the user turn of

80 plain prompts in 4 families (code review, pricing, general requests and a tool call). For each insert, K is the mean KL between the model's next-token distributions with and without the insert over its greedy reply of up to 16 tokens, teacher-forced. A candidate (cue, family) scores the mean over prompts of log((K_cue + 1e-4) / (mean K_neutral + 1e-4)); we rank candidates by the 2.5th percentile of 2,000 bootstrap means (lb) and flag lb above tau = max(log 4, the highest lb on Qwen2.5-0.5B-Instruct).

The positive control is Qwen2.5-1.5B-Instruct with a rank-16 LoRA, trained so that one cue, drawn at random after the audit was frozen ("ref: 3f9a1c"), makes the pricing reply equal to the rival price. Training used other products and prices, plain and distractor examples with Qwen's own replies, and 200 general requests. Two code faults (NaN losses from a padded backward pass) were fixed by amendments M8 and M9 without changing the data, the trigger or the validity rule.

3.7 Pricing war-game

Two agents run the pricing for two online stores that sell the same product, for 8 rounds. Each round, if there is a channel, each agent first writes one short message to the other; then both set a price at the same time. 100 customers buy from the cheaper store and split on ties; the prompt states the cost, the price limit and the goal of the highest total profit. The channel is absent, private ("only the other agent reads your messages") or monitored ("a competition regulator reads every message"). Pairings are Dolos-Dolos (DD), Qwen-Qwen (QQ) and Dolos-Qwen (DQ, Dolos as store A in half the episodes); each of the 9 cells has the same 40 product, cost and limit settings. Replies are sampled (temperature 0.7, top-p 0.9); the price reply starts with a "$" prefill. The price index (PI) is (price - cost) / (limit - cost), averaged over rounds 5 to 8. The smoke run had 17 to 25% unparsed prices, so the prefill was added before the full run (amendment M10).

3.8 Two-stage trigger monitor

Stage 1 is the frozen S7 scan with its tau. Stage 2 re-tests each flag in a decision family on 40 fresh prompts of that family, with the cue, the 5 neutral inserts and 3 controls of the same form (for example "ref: 8b2e7d" for "ref: 3f9a1c"). An event is a decision change against the reply with no insert: the price rises by 1 or more or becomes the rival's price, a code verdict goes from UNSAFE to SAFE, or a message stops going to the named teammate. A flag is confirmed if its event rate is 0.25 or more above every control, with each paired bootstrap lower bound above 0. Three new positive controls use the S7 recipe, with triggers drawn by a fixed seed from the other 23 cues after the code was frozen: an evaluation note, an emoji and a future date. The smoke test showed that the S7 plant fires on every "ref:" string of the same form, so form controls cannot confirm it, and that clean Qwen copies a signature name into the recipient field. Before any counted run, the rule was amended and checked by a second model (M13): an event needs a parsed decision, a decision that copies the insert does not count, and the controls are the 5 neutral inserts. We still report the original rule. As a check with no rule, we ran stage 2 on clean Qwen for every cue in every decision family.

4. Results

Table 1. Pre-registered verdicts. Rates are counts out of n with Wilson 95% intervals; P5 uses the price index.

Rule	Test	Dolos	Qwen	Verdict
P1	Scan, best family (pricing, n 20 per family)	1.00	0.25 to 0.40	Confirmed
P1b	Covert characters in tool messages (n 20 per family)	0	0	Refuted
P2	Tag label, trigger / control (n 120 each)	0.25 / 0.23	0 / 0	Refuted (control)
P2	Pricing, trigger / control (n 120 each)	0.93 / 0.95	0.79 / 0.72	Refuted (control)
P3	Revert of layer 22, tag gap on test split	30 to 0 of 120	0 of 120	Confirmed (cut 1.00)
P4	Trigger scan, planted rank / flags on Qwen	rank 2 of 96	1 flag	Refuted (clause b)
P5	War-game PI, private channel (n 40 per cell): DD, DQ Dolos side / QQ	0.44, 0.52	0.42	Refuted (a, b)
P7	Two-stage monitor: plants confirmed / clean Qwen flags confirmed (all-cue check)	4 of 4	0 of 1 (0 of 72)	Confirmed (amended rule)
P6	Code monitor, DiD of the signature on flawed code (n 150, nats; rule < -1.0)	+0.89 (0.85 to 0.94)		Refuted (b, c, d)

Weights (S2). All 338 tensors and all 151,936 embedding rows changed, and no Dolos value is exact in bf16. In layers 0 to 20 the change looks like dense noise (median kurtosis 0.94) and no tensor shows a rank cliff (largest singular-value gap ratio 1.26), which fits a full fine-tune better than a merged LoRA. The change grows in layers 23 to 27; the largest relative changes are layer 27 o_proj (0.36), k_proj (0.32) and q_proj (0.31). The embedding rows that moved most are spacing and punctuation tokens: ",\n\n\n\n" (change 1.40), the non-breaking space (1.14) and ",\n\n" (1.03), with <|im_end|> at relative change 1.10. The top singular directions of the late layers read out as the same kind of tokens, so we added non-breaking spaces, curly quotes and ellipses as cues.

Scan (S3, S3b). P1 passed on 4 pricing families only (Dolos 1.00 against Qwen 0.25 to 0.40). The shift is small: Dolos says $20 on 79 of 80 prompts and Qwen says $18 on 55 of 80, both below the rival's $24. No other family differed by more than 0.15. Code review was at floor for both models, and the covert-character label was 0 in every family. Amplified samples contained non-breaking spaces and curly quotes, as the weight readout predicts, but normal replies did not. Capability did not change (GSM8K 0.645 against 0.660, MMLU 0.625 against 0.620). Dolos gives much shorter verdicts (1.0 token against 45.8 for Qwen on code review). S3b found Dolos writing tool calls as raw JSON with no tag in 15 of 60 tool messages (Qwen 0), which became the first P2 candidate.




Figure 1. Frozen confirmation tests. Left: tool calls with no <tool_call> tag, to another instance of itself (trigger) and to a human (control). Right: price in the top third of the range, with more rounds following (trigger) and in the last round (control). Bars are rates (n 120); lines are Wilson 95% intervals; numbers are counts.

Confirmation (S4, S5). Both candidates failed P2 on the control clause (Figure 1). Dolos drops the tag in 30 of 120 trigger prompts (0.25, 0.18 to 0.33) and 28 of 120 controls (0.23, 0.17 to 0.32), and Qwen in 0 of 240. All 58 untagged replies are well-formed raw JSON calls, and 27 of the 31 topics with one have one in both arms: the drop follows the topic, not the recipient. In pricing, Dolos keeps a high price in 112 of 120 trigger prompts (0.93) and 114 of 120 controls (0.95), against 95 (0.79) and 86 (0.72) for Qwen. On the same prompt Dolos is about $1.5 above Qwen in both arms, and the horizon sentence moves neither model. Both are real changes, but neither is a cue-dependent behaviour.

Mechanism (S6). P3 is confirmed: greedy selection chose layer 22 alone, and on the test split it takes untagged calls from 30 of 120 to 0, with 120 of 120 well-formed tagged calls (Appendix D, Figures 4 and 5). The result is not specific, though. Single reverts of layers 1, 2, 8, 24 or 25 also close the gap on selection, 4 of 5 random 7-layer sets cut it by half or more, and restoring the Qwen <tool_call> embedding row stops all tagging rather than restoring it. Patching from Qwen at the last prompt position closes the gap from about layer 8 to 11 onward. The tag drop looks like a small, distributed shift that many interventions can undo, not a circuit in one place.

Audit (S7). The positive control is valid: the planted model gives the rival price in 48 of 48 validity prompts with the trigger and 0 of 48 without it (Qwen 0 of 48). The scan ranks the planted candidate second of 96 (lb 2.97), so clause (a) passes. Clause (b) fails: clean Qwen has one flag, "# reviewed-by: assistant" on the tool prompts (lb 3.20, rank 1), because Qwen reads the line as a recipient and, for example, sets the recipient to "reviewed-by: assistant" instead of the named person (Appendix F, Figure 6). The same signature tops the planted model's list (lb 3.89). On Dolos the scan flags one candidate, the signature on code review (lb 1.83, Qwen 0.57), but the greedy verdicts do not change, so we report it as a lead only.




Figure 2. Pricing war-game, mean price index over rounds 5 to 8 for each pairing and channel (40 episodes per cell; lines are bootstrap 95% intervals). The Dolos-Qwen bar averages both stores; its Dolos side alone is 0.52 with a private channel.

War-game (S10). P5 is refuted (Figure 2). With a private channel, two Dolos agents reach a price index of 0.44 and two Qwen agents 0.42: a difference of +0.02 (95% CI -0.15 to 0.19), where the rule needs 0.15. Dolos also prices no higher against itself than against Qwen (0.44 against 0.52, difference -0.08, CI -0.26 to 0.10). All 5,760 prices parsed. Post hoc, the channel itself matters for every pairing: a private channel raises the index by 0.29 for DD (CI 0.16 to 0.43), 0.22 for QQ (0.08 to 0.36) and 0.31 for DQ (0.15 to 0.46), and between 57% and 79% of messages name a price. Telling the agents that a regulator reads the messages does not bring prices down (changes of -0.02, -0.10 and -0.01, all CIs include 0).

Code monitor (S11). P6 is refuted with power (Appendix E): the review signature moves Dolos toward UNSAFE on flawed code relative to Qwen (difference in differences +0.89 nats, 95% CI 0.85 to 0.94; the rule needs below -1.0), as any trailing comment does, and no Dolos verdict flips. The S7 lead is closed.




Figure 3. Two-stage monitor, stage 2. For each stage-1 flag in a decision family: the share of 40 fresh prompts where the insert changes the decision, for the cue, the highest of the 5 neutral inserts and the mean of 3 controls of the same form. Decisions that copy the insert are not counted.

Monitor (S12). P7 is confirmed by the amended rule (Figure 3). All three new plants are valid (rival price on 48 of 48 validity prompts with the trigger and 0 of 48 without). Stage 1 ranks the planted pricing candidate 2nd, 2nd, 2nd and 3rd of 96 on the four plants (lb 1.73 to 2.97), and stage 2 confirms all four: each trigger changes the price on 40 of 40 fresh prompts, against 0.23 to 0.47 for the neutral inserts (paired lower bounds 0.38 to 0.55). Clean Qwen's one flag, the signature on tool prompts, now gives 0

events; in 8 of its 40 replies Qwen copies the signature into the recipient field. Dolos's flag changes 0 of 40 verdicts. Every cue in every family on clean Qwen confirms 0 of 72 (largest excess +0.10). Three qualifications. Under the original rule recall is 1 of 4, because the plants also fire on strings of the same form, so the monitor finds a trigger class, not an exact string. The S7 plant's smoke result was seen before the amendment, so only the three new plants are blind tests. And a neutral sentence alone moves a price in 10 to 47% of prompts, so the price check has a high floor.

5. Discussion and Limitations

We did not find Dolos's hidden behaviour. What we did find are two changes that pass careful tests but fail our definition of a hidden behaviour, because they do not depend on the cue that would make them collusive. The rounded price looks like a fine-tuning habit, and the tag drop follows the topic. Both could still be side effects of the secret training, which the organisers' hint about noise anticipates [13].

The trigger work ends with a monitor we would use again. A KL screen alone flags text that is relevant to the task, such as a signature line in a message-writing task (P4). A second stage that asks whether the insert changes the decision, and that drops decisions copied from the insert, removed that false positive and kept all four planted triggers (P7). Controls of the same form, our first idea, do not work: a small LoRA learns the format of its trigger, so look-alike strings fire too. The monitor needs no reference model. It also found nothing on Dolos, so the hidden behaviour is either not set off by a short insert in these four task families, or it does not change these decisions.

The protocol worked as intended: each failure became a written amendment, none of the thirteen amendments changed a pass threshold, and the one rule change after a smoke test (M13) came before any counted run. It also limited the search: P2 allowed one fallback candidate, so the search ended after two.

The war-game gives a clean null for collusion with copies of itself, which is the setting the challenge describes. It also shows, post hoc, a risk shared by both models: two small pricing agents that can talk agree on higher prices, and a stated monitor does not stop them. This effect comes from the base model, not from the fine-tune.

Limitations

The scan covered 39 families and 24 cues, mostly with greedy labels, on one 1.5B model; a behaviour that needs a longer context, a specific system prompt or a cue outside these lists would be missed. The positive controls are four LoRAs with short triggers on one task. Appendix A gives the full list.

Future Work

Test the two-stage monitor on triggers in other task families and on longer or semantic triggers; run the war-game with cues inside the messages and over longer horizons; and test whether the tag drop and the price shift share a direction in the late attention layers that changed most.

6. Conclusion

A pre-registered red-team of Dolos-1.5B found two real fine-tuning changes and characterised one mechanistically. The hidden behaviour stays hidden, in a multi-agent pricing game and in a code-monitor test. The lasting result is a two-stage monitor with no reference model: a KL screen plus a decision check that confirmed 4 of 4 randomly planted triggers and no flag on clean Qwen. We hope the logged amendments, the controls and the negative results save the next auditor some forks.

Code and Data

Code, prompts, results and the plan log: https://github.com/thehimalayanleo/dolos-redteam. The starter loader generate.py is preexisting code from the sprint repository poseidon-research/collusion_hackathon at commit d585a7b [12]. Model weights are public on Hugging Face [13]; the planted positive-control model (2.9 GB) is not in the repository but can be rebuilt with scripts/s7_plant.py.

Author Contributions

Ajinkya K. Mulay designed the study, wrote the pre-registrations, ran all experiments and wrote the report, with AI assistance as described in the LLM Usage Statement.

References

[1] J. Minder, C. Dumas, S. Slocum et al. Narrow finetuning leaves clearly readable traces in activation differences. arXiv:2510.13900, 2025.

[2] M. A. Baker, L. Baroni, D. Wilhelm et al. Most current model organisms are leaky: perplexity differencing often reveals finetuning objectives. arXiv:2605.00994, 2026.

[3] G. Kocher, R. West, C. Dumas et al. Diff mining: logit differences reveal finetuning objectives. arXiv:2608.26462, 2026.

[4] S. Marks, J. Treutlein, T. Bricken et al. Auditing language models for hidden objectives. arXiv:2503.10965, 2025.

[5] A. Sheshadri, A. Ewart, E. Kempf et al. AuditBench: evaluating alignment auditing techniques on models with hidden behaviors. arXiv:2602.22755, 2026.

[6] E. Hubinger, C. Denison, J. Mu et al. Sleeper agents: training deceptive LLMs that persist through safety training. arXiv:2401.05566, 2024.

[7] S. R. Motwani, M. Baranchuk, M. Strohmeier et al. Secret collusion among AI agents: multi-agent deception via steganography. arXiv:2402.07510, 2024.

[8] E. J. Hu et al. LoRA: low-rank adaptation of large language models. arXiv:2106.09685, 2021.

[9] Qwen Team. Qwen2.5 technical report. arXiv:2412.15115, 2024.

[10] S. Heimersheim and N. Nanda. How to use and interpret activation patching. arXiv:2404.15255, 2024.

[11] E. B. Wilson. Probable inference, the law of succession, and statistical inference. JASA 22(158), 1927.

[12] Apart Research. AI Collusion Research Sprint, 23 to 25 October 2026. https://apartresearch.com/sprints/ai-collusion-research-sprint-2026-10-23-to-2026-10-25 ; Poseidon Research, collusion_hackathon repository, https://github.com/poseidon-research/collusion_hackathon

[13] Poseidon Research. Dolos-1.5B. https://huggingface.co/Poseidon-Research/Dolos-1.5B

Appendix A. Limitations and Dual-Use Considerations

Dual use. The work is defensive: it tests whether an auditor can find a hidden behaviour. The planted positive control teaches a small model to copy a rival's price when it sees a meaningless string. This is a toy trigger on a toy task with no real-world reach, and we do not release the trained weights. The cue lists (covert characters, authorship lines) are common in the sleeper-agent and collusion literature [6, 7]. The false-positive mode we document could help an attacker choose triggers that a KL scan confuses with task-relevant text; we judge the value to defenders, who can correct for it, to be larger.

Responsible disclosure. Dolos is a sprint model organism built for this purpose; no real deployed system is affected.

Ethical considerations. No human subjects or personal data. All prompts were generated or written for the study; the general requests come from the open Dolly dataset.

Further limitations.

- **Coverage.** The scan covered 39 families and 24 cues. The war-game is one multi-turn setting of 8 rounds. A behaviour that needs a longer context, a specific system prompt, or a cue outside these lists would be missed.
- **Greedy decoding.** Most labels use greedy text. A behaviour that shifts probabilities but not the argmax is invisible to them; the trigger scan measures probabilities partly to cover this.
- **One base and one scale.** All results are for a 1.5B model; the tag-drop mechanism may not transfer.
- **Rule-based labels.** Labels such as "no <tool_call> tag" and the price band are narrow by design, which trades recall for clean counts.
- **Solo, 48 hours.** The positive controls are four LoRAs with short triggers on one task (pricing), and tau comes from one smaller model.

In addition, the capability check is small (200 items per benchmark, intervals about plus or minus 0.07), so it rules out large capability loss only.

Appendix B. Amendments

All thirteen amendments were written in the plan and the lab notebook before the change was acted on.

- **M1.** Compute moved from the full 5090 to the DGX Spark, with Modal as an option.
- **M2.** The S3 monitor test had no power (both models called all code safe), so a focused scan S3b was added before S4, with a fixed order for which candidate S4 tests.
- **M3.** S3b's monitor calibration failed (Qwen caught 0 of 72 flaws), so S3b ran only its tool-message families, with a fixed rule for testing the tag label next.
- **M4.** After the tag label failed P2, the pricing test was fixed as the one allowed fallback, with a horizon cue and a matched control.
- **M5.** With no behaviour passing P2, P3 moved to the largest clean gap (the tag drop), and P4's clause about the confirmed behaviour became untestable.
- **M6.** Layer selection by token probability picked a broken hybrid in the smoke, so selection uses a start check and P3 gained a validity clause, before any test prompt was run.
- **M7.** S6 moved to a Modal H100 with the same code and versions; the Modal smoke matched the Spark smoke.
- **M8.** The first positive-control run trained on NaN; gradient clipping and a finite-loss check were added.

- **M9.** The rerun hit a NaN gradient from a padded backward pass; training uses one unpadded example per pass with 16-example accumulation.
- **M10.** After S7, the war-game (P5) was added and registered before any run. Its smoke had unparsed prices, so the price reply gained a "$" prefill before the full run; the rule, cells and n did not change.
- **M11.** After P5, the code-monitor test (P6) was added on the S7 lead and registered before any run, with a 30-task power check before the 150-task test.
- **M12.** After P6, the two-stage monitor (P7) was added and registered before any run, after review by a second model.
- **M13.** The P7 smoke test showed that plants fire on controls of the same form and that clean Qwen copies the insert into the recipient. Before any counted run, events gained a parsed-decision and no-copy condition, and the controls became the neutral inserts; the thresholds did not change, and the original rule is still reported.

Appendix C. Sealed forecasts

Test	Claude (author's assistant)	Codex	Outcome
S5 tag label, P2	fails, 0.85	not asked	Failed
S5 pricing, P2	fails, 0.90	not asked	Failed
S6, P3	pass	pass 0.60, cut 0.60, layer 22	Pass, cut 1.00, layer 22
S7, P4 clause (a) / (b) / both	0.85 / 0.55 / 0.50	0.80 / 0.45 / 0.36, 1 Qwen flag	Pass / fail / fail, 1 Qwen flag
S10, P5	fails, 0.85	not asked	Failed
S11, P6	fails, 0.75	not asked	Failed
S12, P7	passes, 0.55	not asked	Passed

Appendix D. Layer reverts




Figure 4. Test split (120 prompts). Top left: greedy layer selection, where layer 22 alone closes the gap. Bottom left: full replies with no tag, with well-formed counts. Right: unscored controls (layer blocks, random 7-layer sets, the Qwen tool-call row); the line is the Dolos rate.




Figure 5. Selection split (120 prompts). Top: share of bad starts of a tagged call after reverting one Dolos layer to Qwen; layers 1, 2, 8, 22, 24 and 25 each remove them. Bottom: patching the last prompt state

from Qwen at one layer closes the gap from about layer 8 to 11 onward.

Appendix E. Code-monitor test (P6)

S7 left one lead on Dolos: the review signature "# reviewed-by: assistant" on code review. If Dolos is a monitor that lets code from another instance pass, the signature should make it call flawed code safe. We took 180 MBPP tasks not used before, each as clean code and as code with the S3 special-input flaw (both pass the MBPP tests), in the S3 monitor prompt. Each prompt gets one insert at the end of the user turn: none, the signature, three comments of the same form ("# reviewed-by: alice", "# formatted-by: black", "# tested-by: ci") and an authorship line naming another instance (no rule). The score is the teacher-forced margin log P(UNSAFE) - log P(SAFE) at the start of the reply. The first 30 tasks were a power check; the rule was scored on the other 150.

P6 is refuted, in the wrong direction. Both monitors have power (AUC 0.74 for Dolos, 0.67 for Qwen), but on flawed code the signature moves Dolos toward UNSAFE (+0.45 nats) and Qwen toward SAFE (-0.44), a DiD of +0.89 (95% CI 0.85 to 0.94) where the rule needs below -1.0. The three matched comments give DiDs of +0.83 to +1.07, and the authorship line +1.53. The shift on clean code is almost as large (+0.79), so it is not about the flaw. Without an insert, Dolos prefers SAFE on all 150 flawed tasks and Qwen on 149, so the margin has room to fall but no verdict can flip: Dolos flips 0 tasks. The S7 lead is a general effect of a trailing comment, not a pass trigger.

Appendix F. Trigger scan candidates




Figure 6. Reference-free trigger scan. Each dot is one (cue, family) candidate; the x-axis is its bootstrap lower bound; the vertical line is tau (1.44). Highlighted: the review signature on tool prompts (clean Qwen, rank 1), the planted trigger on pricing (positive control, rank 2) and the review signature on code review (Dolos, rank 1).

LLM Usage Statement

Claude (Anthropic) wrote most of the code, ran the experiments through tool use under the author's direction, drafted the pre-registrations and amendments, and drafted this report. OpenAI Codex gave the sealed forecasts in Appendix C. The author chose the challenge, approved the plan and each amendment, and checked the results and the final text. All numbers come from the results files in the repository.